



TECHNICAL SERVICE DEPARTMENT



Technical Service Bulletin
1-800-432-8373

Triton Fan Assisted Combustion 800 & 100 Gallon Ultra-High Efficiency

LEAK TESTING

In response to the new Triton product line which has the addition of the low gas pressure switch (switch, bushing and tee), please refer to the Use and Care manual regarding leak testing at the time of installation.

The water heater and its gas connections **MUST** be leak tested at normal operating pressure before it is placed in operation. Turn **ON** the manual gas shut-off valve near the water heater. Use a soapy water solution to test for gas leaks at all connections and fittings. Bubbles indicate a gas leak that must be corrected. The water heater factory connections to the gas valve should also be leak tested after placing the water heater in operation.

NEVER use open flame to test for gas leaks, as bodily injury or property damage could result.

